City of Binghamton Water Street Development Corporation

Special Meeting Wednesday April 12, 1:00 PM Mayor's Conference Room, City Hall, 4th floor

PROPOSED AGENDA

I.	Call	to	order

II. Old Business

None


III. New Business:

RESOLUTION 23-6 A RESOLUTION OF THE CITY OF BINGHAMTON WATER STREET DEVELOPMENT CORPORATION TO ACCEPT A GARAUNTEED MAXIMUM PRICE OF \$22,060,245 FOR THE DEVELOPMENT OF THE PARKING GARAGE AND \$3,050,300 FOR THE SIXTH FLOOOR PODIUM BY UNITED - PIKE DEVELOPMENT JV, LLC

- VI. Update on Water Street Parking Ramp Project
- VII. Adjourn

City of Binghamton: Water Street Garage

Binghamton, New York







Contents

DRAWINGS - REVISED

ASSUMPTIONS & CLARIFICATIONS - REVISED

ALTERNATE LIST & DESCRIPTIONS

Drawings

Pike

Water St Municipal Parking Garage Contract Document List $\underline{4/5/2023}$

DOCUMENT NUMBER	DOCUMENT TITLE	ISSUE DATE	REV. 1	REV. 2	REV. 3
General					
A-001	SYMBOLS, ABBREVIATIONS & GEN. NOTES	1/31/2023	2/23/2023		
Code Review					
LS-00	LIFE SAFETY	Not Issued	2/23/2023		
LS-01	LIFE SAFETY PLANS	Not Issued	2/23/2023		
LS-02	LIFE SAFETY PLANS	Not Issued	2/23/2023		
LS-03	LIFE SAFETY PLANS	Not Issued	2/23/2023		
Civil					
C-010	EXISTING SITE CONDITIONS	1/31/2023	2/23/2023		
C-020	DEMOLITION PLAN	1/31/2023	2/23/2023	3/7/2023	
C-100	LAYOUT PLAN	1/31/2023	2/23/2023	3/1/2023	
C-110	GRADING PLAN	1/31/2023	2/23/2023		
C-120	UTILITY PLAN	1/31/2023	2/23/2023	3/7/2023	
C-130	EROSION AND SEDIMENT CONTROL PLAN	Not Issued	2/23/2023		
C-200	CITY OF BINGHAMTON STANDARD DETAILS	1/31/2023	2/23/2023		
C-210	STANDARD DETAILS	Not Issued	2/23/2023		
C-220	SPECIFICATIONS	Not Issued	2/23/2023		
Structural					
S-001	NOTES, DESIGN CRITERIA & SHEET INDEX	1/31/2023	2/23/2023		
S-002	NOTES, ABBREVIATIONS & SYMBOLS	1/31/2023	2/23/2023		
S-010	SPECIAL INSPECTION SCHEDULE	1/31/2023	2/23/2023		
S-020	FLOOR LOAD MAPS	1/31/2023	2/23/2023		
S-100	EXISTING FOUNDATION PLAN	Not Issued	2/23/2023		
S-101	FIRST FLOOR FOUNDATION PLAN	1/31/2023	2/23/2023		
S-101a	FIRST FLOOR FOUNDATION PLAN - AREA A	Not Issued	2/23/2023		
S-101b	FIRST FLOOR FOUNDATION PLAN - AREA B	Not Issued	2/23/2023		
S-102	SECOND FLOOR FRAMING PLAN	1/31/2023	2/23/2023		
S-103	THIRD FLOOR FRAMING PLAN	1/31/2023	2/23/2023		
S-104	FOURTH FLOOR FRAMING PLAN	1/31/2023	2/23/2023		
S-105	FIFTH FLOOR FRAMING PLAN	1/31/2023	2/23/2023		
S-106	SIXTH FLOOR FRAMING PLAN	1/31/2023	2/23/2023		
S-106a	SIXTH FLOOR FRAMING PLAN - AREA A	1/31/2023	2/23/2023		
S-106b	SIXTH FLOOR FRAMING PLAN - AREA B	1/31/2023	2/23/2023		
S-107	SEVENTH LEVEL FRAMING PLAN	1/31/2023	2/23/2023		
S-200	PRECAST COLUMN SCHEDULE	1/31/2023	2/23/2023		
S-210	PRECAST SHEAR WALL ELEVATIONS	1/31/2023	2/23/2023		
S-300	TYPICAL FOUNDATION DETAILS TYPICAL PILECAP DETAILS	1/31/2023	2/23/2023		
S-301	TYPICAL FOUNDATION DETAILS PILECAP DETAILS	1/31/2023	2/23/2023		
S-302	TYPICAL FOUNDATION DETAILS PILECAP DETAILS	1/31/2023	2/23/2023		
S-303	TYPICAL FOUNDATION DETAILS PILECAP DETAILS	1/31/2023	2/23/2023		
S-304	PILECAP DETAILS	Not Issued	2/23/2023		
S-320	TYPICAL DETAILS	1/31/2023	2/23/2023		
S-321	TYPICAL DETAILS	1/31/2023	2/23/2023		
S-322	TYPICAL DETAILS	1/31/2023	2/23/2023		
S-323	TYPICAL DETAILS	1/31/2023	2/23/2023		
Architectural		100707070	7.75.7		
A-101	FIRST FLOOR PLAN	1/31/2023	2/23/2023	3/1/2023	
A-102	SECOND FLOOR PLAN	1/31/2023	2/23/2023	31112023	
A-103	THIRD FLOOR PLAN	1/31/2023	2/23/2023		
A-104	FOURTH FLOOR PLAN	1/31/2023	2/23/2023		
A-105	FIFTH FLOOR PLAN	1/31/2023	2/23/2023		
A-106	SIXTH FLOOR PLAN	1/31/2023	DELETED		
A-107	SEVENTH FLOOR PLAN	1/31/2023	DELETED		
A 108	EIGHTH FLOOR PLAN	1/31/2023	DELETED		
11.100	S. S. L. L. S. S. L.	113112023	DELLIED		



DOCUMENT NUMBER	DOCUMENT TITLE	ISSUE DATE	REV. 1	REV. 2	REV. 3
General	DOCUMENT TILE	ISSUE DATE	KEV. I	REV. 2	REV. 3
A-109	NINETH FLOOR PLAN	1/31/2023	DELETED		
A-110	TENTH FLOOR PLAN	1/31/2023	DELETED		
A-111	ROOFPLAN	1/31/2023	DELETED		
	EXTERIOR ELEVATIONS	1/31/2023	2/23/2023		
A-200		1/31/2023	2/23/2023	3/1/2023	
A-201	EXTERIOR ELEVATIONS	1/31/2023		3/1/2023	
A-250	BUILDING SECTIONS PLUI DING SECTIONS		DELETED		
A-251	BUILDING SECTIONS ENLANGED FLOOD PLANG	1/31/2023	DELETED		
A-300	ENLARGED FLOOR PLANS	1/31/2023	2/23/2023	3/1/2023	
A-401	FIRST FLOOR REFLECTED CEILING PLAN FIRST & SECOND FLOOR REFLECT. CEILING PLAN	1/31/2023	2/23/2023		
A-402	SECOND FLOOR REFLECTED CEILING PLAN THIRD & FOURTH FLOOR REFLECT. CEILING PLAN	1/31/2023	2/23/2023		
A-403	THIRD FLOOR REFLECTED CEILING PLAN	1/31/2023	DELETED		
A-404	FOURTH FLOOR REFLECTED CEILING PLAN	1/31/2023	DELETED		
A-405	FIFTH FLOOR REFLECTED CEILING PLAN	1/31/2023	DELETED		
A-410	ENLARGED RFLECTED CEILING PLAN	1/31/2023	DELETED		
A-500	VERT. CIRC. NORTH STAIR/ELEV.	1/31/2023	2/23/2023		
A-501	VERTICAL CIRCULATION SOUTH STAIR/ELEV.	1/31/2023	2/23/2023		
A-502	VERTICAL CIRCULATION SOUTH ELEV. & MAINT, STAIR	1/31/2023	2/23/2023		
A-503	MISC. STAIRS	Not Issued	2/23/2023		
A-510	VERTICAL CIRCULATION SECTIONS	1/31/2023	2/23/2023		
A-511	VERTICAL CIRCULATION SECTIONS	1/31/2023	2/23/2023		
A-600	WALL SECTIONS	1/31/2023	2/23/2023		
A-601	WALL SECTIONS	1/31/2023	2/23/2023		
A-602	WALL SECTIONS	Not Issued	2/23/2023		
A-700	ENLARGED PLANS & DETAILS	Not Issued	2/23/2023		
A-801	DOOR SCHEDULE	Not Issued	2/23/2023		
A-803	DOOR TYPES & STOREFRONT ELEVATIONS AND DETAILS	1/31/2023	DELETED		
Parking					
PK-101	FIRST FLOOR PARKING PLAN	Not Issued	2/23/2023		
PK-102	SECOND FLOOR PARKING PLAN	Not Issued	2/23/2023		
PK-103	THRID FLOOR PARKING PLAN	Not Issued	2/23/2023		
PK-104	FOURTH FLOOR PARKING PLAN	Not Issued	2/23/2023		
PK-105	FIFTH FLOOR PARKING PLAN	Not Issued	2/23/2023		
PK-200	DETAILS	Not Issued	2/23/2023		
		1.07.0000			
Architectural Parking AP-102	ARCHITECTURAL PARKING PLANS	Not Issued	2/23/2023		
AP-102	ARCHITECTURAL PARKING PLANS	Not Issued	2/23/2023		
AP-103	ARCHITECTURAL PARKING PLANS	Not Issued	2/23/2023		
AP-201	SIGNAGE DETAILS - ARCHITECTURAL PARKING	Not Issued	2/23/2023		
AP-202	SIGNAGE DETAILS - ARCHITECTURAL PARKING SIGNAGE DETAILS - ARCHITECTURAL PARKING	Not Issued	2/23/2023		
AP-203	SIGNAGE DETAILS - ARCHITECTURAL PARKING SIGNAGE DETAILS - ARCHITECTURAL PARKING	Not Issued	2/23/2023		
AP-251	SIGN MOUNTING DETAILS - ARCHITECTURAL PARKING	Not Issued	2/23/2023		
	SIGN MOUNTING DETAILS - ARCHITECTURAL FARRING	Not issued	2/23/2023		
Mechanical	LECENDO & ADDREVIATIONO	1/31/2023	2/23/2023		
M-001	LEGENDS & ABBREVIATIONS		DELETED		
M004	FIRST FLOOR DEMOLITION PLAN - PLUMBING & PIPING	1/31/2023			
M-111	PARKING GARAGE FIRST LEVEL PLAN	Not Issued	2/23/2023		
Plumbing P-001	LEGENDS & GENERAL NOTES	1/31/2023	2/23/2023		
P-110	FOUNDATION PLAN	1/31/2023	2/23/2023	3/8/2023	
P-111	PARKING GARAGE FIRST LEVEL PLAN	1/31/2023	2/23/2023	3/8/2023	
P-112	PARKING GARAGE SECOND LEVEL PLAN	1/31/2023	2/23/2023	31012023	
P-113	PARKING GARAGE THIRD LEVEL PLAN	1/31/2023	2/23/2023		
P-114	PARKING GARAGE FOURTH LEVEL PLAN	1/31/2023	2/23/2023		
P-115	PARKING GARAGE FIFTH LEVEL PLAN	1/31/2023	2/23/2023		
P-401	SCHEDULES	1/31/2023	2/23/2023		
P-401 P-501	DETAILS	1/31/2023	2/23/2023	2 10 10 5 7 7	
	DEINIE	1/31/2023	212312023	3/8/2023	
Fire Protection					



DOCUMENT					
NUMBER	DOCUMENT TITLE	ISSUE DATE	REV. 1	<u>REV. 2</u>	REV. 3
General					
FP-001	LEGENDS & GENERAL NOTES	1/31/2023	2/23/2023	3/8/2023	
FP-111	PARKING GARAGE FIRST LEVEL PLAN	1/31/2023	2/23/2023	3/8/2023	
FP-112	PARKING GARAGE SECOND LEVEL PLAN	1/31/2023	2/23/2023	3/8/2023	
FP-113	PARKING GARAGE THIRD LEVEL PLAN	1/31/2023	2/23/2023		
FP-114	PARKING GARAGE FOURTH LEVEL PLAN	1/31/2023	2/23/2023	3/8/2023	
FP-115	PARKING GARAGE FIFTH LEVEL PLAN	1/31/2023	2/23/2023	3/8/2023	
FP-301	RISER DIAGRAM	1/31/2023	2/23/2023	3/8/2023	
FP-501	DETAILS	1/31/2023	2/23/2023	3/8/2023	
Electrical E-001	LEGENDS & ABBREVIATIONS	1/31/2023	2/23/2023		
E-100	PARKING GARAGE FIRST LEVEL PLAN CONDUIT ROUTING	1/31/2023	2/23/2023		
E-111	PARKING GARAGE FIRST LEVEL PLAN	1/31/2023	2/23/2023		
E-112	PARKING GARAGE SECOND LEVEL PLAN	1/31/2023	2/23/2023		
E-113	PARKING GARAGE THIRD LEVEL PLAN	1/31/2023	2/23/2023		
E-114	PARKING GARAGE FOURTH LEVEL PLAN	1/31/2023	2/23/2023		
E-115	PARKING GARAGE FIFTH LEVEL PLAN	1/31/2023	2/23/2023		
E-116	PARKING GARAGE SIXTH LEVEL PLAN	Not-Issued	DELETED		
E-301	ONE-LINE DIAGRAM	1/31/2023	2/23/2023		
E-401	SCHEDULES	1/31/2023	2/23/2023		
E-402	PANELBOARD SCHEDULES	1/31/2023	2/23/2023		
E-403	PANELBOARD SCHEDULES	Not Issued	2/23/2023		
E-501	DETAILS	1/31/2023	2/23/2023		
E-502	DETAILS	1/31/2023	2/23/2023		
E-503	DETAILS	Not Issued	2/23/2023		
E-504	DETAILS	Not Issued	2/23/2023		
SUPPLEMENTAL DRAWINGS					
	PRELIMINARY FOUNDATION CONCEPT (S-100 & S-101) FOUNDATION PLAN FROM WATER STREET 1968 - REFERENCE ONLY GRID LINE GI - PROGRESS PRINT NOTE FOR CONSTRUCTION	01/27/23 03/03/23			03/31/23
	SPECIFICATIONS				
	DIVISION 03 - CONCRETE				
03 30 00	CAST-IN-PLACE CONCRETE	Not Issued	02/23/23		
03 41 00	PRECAST STRUCTURAL CONCRETE	Not Issued	02/23/23		
	DIVISION 04 - MASONRY				
04 22 00	CONCRETE UNIT MASONRY	Not Issued	02/23/23		
	DIVISION 05 - METALS	20 12 157			
05 12 00	STRUCTURAL STEEL FRAMING	Not Issued	02/23/23		
05 31 00	STEEL DECKING	Not Issued	02/23/23		
05 40 00	COLD-FORMED METAL FRAMING	Not Issued	02/23/23		
05 52 13	PIPE AND TUBE RAILINGS	Not Issued	02/23/23		
	DIMICION OF WOOD IN ACTION A LOOMPORTED				
06.10.00	DIVISION 06 - WOOD, PLASTICS, and COMPOSITES	Not Issued	00/02/02		
06 10 00	ROUGH CARPENTRY	Not Issued	02/23/23		
06 16 00	SHEATHING	INOT ISSUED	02/23/23		
	DIVISION 07 - THERMAL and MOISTURE PROTECTION				
07 14 16	COLD FLUID-APPLIED WATERPROOFING	Not Issued	02/23/23		
07 18 00	TRAFFIC COATINGS	Not Issued	02/23/23		
07 18 00	FLUID-APPLIED MEMBRANE AIR BARRIERS	Not Issued			
07 42 43.13	WOOD VENEER LAMINATE WALL SIDING	Not Issued	02/23/23 02/23/23		
07 42 43.13	ETHYLENE-PROPYLENE-DIENE-MONOMER (EPDM) ROOFING	Not Issued	02/23/23		
31 33 23	The real party and the second		02123123		



DOCUMENT				No. of the Control of	
NUMBER	<u>DOCUMENT TITLE</u>	ISSUE DATE	<u>REV. 1</u>	<u>REV. 2</u>	<u>REV. 3</u>
General		A7 . 7	300000		
07 62 00	SHEET METAL FLASHING AND TRIM	Not Issued	02/23/23		
07 71 00	ROOF SPECIALTIES	Not Issued	02/23/23		
07 84 43	JOINT FIRESTOPPING	Not Issued	02/23/23		
07 92 00	JOINT SEALANTS	Not Issued	Not Issued	2/23/2023	
	DIMIGION OF OBENINGS				
09 11 12	DIVISION 08 - OPENINGS	Not Issued	02/22/22		
08 11 13	HOLLOW METAL DOORS AND FRAMES OVERHEAD COLLING DOORS	Not Issued	02/23/23		
08 33 23	OVERHEAD COLLING DOORS	Not Issued	02/23/23		
08 33 44	OVERHEAD COILING FIRE CURTAINS	Not Issued	02/23/23		
08 41 13	ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS	Not Issued	02/23/23		
08 71 11	DOOR HARDWARE (DESCRIPTIVE SPECIFICATION)	Not Issued	02/23/23		
08 80 00	GLAZING FIRE PATED CLAZING	Not Issued	02/23/23		
08 88 13	FIRE-RATED GLAZING	Not Issued	02/23/23		
08 91 19	FIXED LOUVERS	1101 133404	02/23/23		
	DIVISION 09 - FINISHES				
09 21 16.23	GYPSUM BOARD SHAFT WALL ASSEMBLIES	Not Issued	02/23/23		
09 96 00	HIGH-PERFORMANCE COATINGS	Not Issued	02/23/23		
	DIVISION 10 - SPECIALTIES	N			
10 14 19	DIMENSIONAL LETTER SIGNAGE	Not Issued	02/23/23		
10 14 23	SIGNAGE	Not Issued	02/23/23		
	DIVIDION 14 CONVEYING FOURNATION				
14.01.00	DIVISION 14 - CONVEYING EQUIPMENT ELECTRIC TRACTION ELEVATORS	Not Issued	02/22/22		
14 21 00	ELECTRIC TRACTION ELEVATORS	1.01 133464	02/23/23		
	DIVISION 22 - PLUMBING				
22 01 00	BASIC PLUMBING AND FIRE PROTECTION REQUIREMENTS	Not Issued	02/23/23		
22 01 50	EXCAVATION AND BACKFILL	Not Issued	02/23/23		
22 01 90	ELECTRIC WIRING	Not Issued	02/23/23		
22 06 00	PIPING SYSTEMS AND ACCESSORIES / INTERIOR BUILDING PIPING	Not Issued	02/23/23		
22 10 00	VALVES	Not Issued	02/23/23		
22 16 00	PUMPS	Not Issued	02/23/23		
22 19 00	PLUMBING IDENTIFICATION	Not Issued	02/23/23		
22 25 00	INSULATION	Not Issued	02/23/23		
22 33 00	DRY FIRE SPRINKLER SYSTEMS	Not Issued	02/23/23		
22 37 50	FIRE STANDPIPE SYSTEMS	Not Issued	02/23/23		
22 41 00	WATER SUPPLY	Not Issued	02/23/23		
22 41 10	WASTE WATER SYSTEMS	Not Issued	02/23/23		
22 45 00	EQUIPMENT	Not Issued	02/23/23		
with the Control of The Control					
	DIVISION 23 - HEATING, VENTILATING, and AIR CONDITIONING (HVAC)				
23 01 00	BASIC MECHANICAL REQUIREMENTS	Not Issued	02/23/23		
23 01 80	MOTORS	Not Issued	02/23/23		
23 06 00	PIPING SYSTEMS AND ACCESSORIES	Not Issued	02/23/23		
23 25 00	INSULATION	Not Issued	02/23/23		
23 78 10	WALL/CEILING MOUNTED ROOM AIR CONDITIONING UNIT (AIR COOLED	Not Issued	02/23/23		
23 83 20	UNIT HEATERS AND CABINET UNIT HEATERS (HYDRONIC AND ELECTRIC)	Not Issued	02/23/23		
23 89 00	SHEET METAL AND DUCTWORK ACCESSORIES CONSTRUCTION	Not Issued	02/23/23		
23 94 50	LOUVERS AND PENTHOUSES	Not Issued	02/23/23		
23 99 00	ADJUSTING AND BALANCING	Not Issued	02/23/23		
	DIVISION 26 - ELECTRICAL	Not Issued	00/00/00		
26 01 00	BASIC ELECTRICAL REQUIREMENTS	Not Issued	02/23/23		
26 01 10	GENERAL PROVISIONS	Not Issued	02/23/23		
26 01 50	WORK INCLUDED BASIC MATERIALS AND METHODS	Not Issued	02/23/23		
26 10 00	BASIC MATERIALS AND METHODS		02/23/23		



DOCUMENT					
NUMBER	DOCUMENT TITLE	ISSUE DATE	<u>REV. 1</u>	<u>REV. 2</u>	<u>REV. 3</u>
General					
26 11 00	RACEWAYS	Not Issued	02/23/23		
26 12 00	CONDUCTORS	Not Issued	02/23/23		
26 12 40	MEDIUM VOLTAGE CABLE	Not Issued	02/23/23		
26 14 00	WIRING DEVICES	Not Issued	02/23/23		
26 32 10	DRY TYPE TRANSFORMERS	Not Issued	02/23/23		
26 42 00	SERVICE ENTRANCE	Not Issued	02/23/23		
26 45 00	GROUNDING	Not Issued	02/23/23		
26 47 00	LOW VOLTAGE POWER DISTRIBUTION EQUIPMENT	Not Issued	02/23/23		
26 48 50	MOTOR STARTERS AND CONTROL DEVICES	Not Issued	02/23/23		
26 50 00	LIGHTING	Not Issued	02/23/23		
26 62 00	POWER GENERATION	Not Issued	02/23/23		
26 72 20	POINT ADDRESSABLE FIRE ALARM SYSTEM	Not Issued	02/23/23		
	DIVISION 31 - EARTHWORK				
31 62 16	STEEL PILES	Not Issued	02/23/23		
	DIVISION 32 - EXTERIOR IMPROVEMENTS				
32 31 13	CHAIN LINK FENCES AND GATES	Not Issued	02/23/23		
32 33 00	SITE FURNISHINGS	Not Issued	02/23/23		
	SUPPLEMENT SPECIFICATIONS				
	SUFFLEMENT SPECIFICATIONS				
	MEMO - 90% PROGRESS DRAWINGS GAPS LIST	01/27/23			
	BINGHAMTON WATER STREET GEOTECHNICAL REPORT	08/24/22			
		00/2-1/22			
	PIKE DOCUMENTS				
1	INVITATION TO BID	02/06/23	02/23/23		
2	INSTRUCTION TO BIDDERS	02/06/23			
3	GENERAL REQUIREMENTS	02/06/23			
4	ALTERNATE LIST AND DESCRIPTIONS				04/04/23
5	CONTRACT DOCUMENTS LIST	02/06/23	02/23/23	03/03/23	04/04/23
6	PREVAILING WAGE SCHEDULE PRC# 2023000912	01/24/23			
7	INSURANCE REQUIREMENTS	. = 2002/000 44 (2000/00) (1 00))			
8	SAMPLE COI CERTIFICATE				
9	TEXTURA INFORMATION	-			
10	SAMPLE MASTER SUBCONTRACT				
11	SAMPLE EXHIBIT AA WORK ORDER SUBCONTRACT	1. - 1			
12	SAMPLE BOND FORMS	-			
14	WATER ST. MILESTONE SCHEDULE				



Assumptions & Clarifications

Pike

Project: Water Street Parking Garage

Page 1 of 5

Assumptions & Clarifications

Schedule

- Construction milestone schedule is attached has not been updated from original proposal
- A letter of Intent for this lump sum proposal is good until April 07, 2023.

General

- Related to the stairs and elevators, the structure will consist of 2 elevator shafts and 2 stair shafts. Stairs will be provided in each stair shaft to service the garage levels. Only 1 elevator, servicing the garage levels will be provided. The installation of the 1 remaining elevator is future work and not included in the cost of work. This elevator has been sized for 10 floors.
- Proposal is based of CJS Architects Construction Documents dated 2-23-23. Please see the attached drawing list. Changes in design and/or scope of work are subject to repricing
- No Boscov work is included in this proposal
- Prevailing wage rates are included
- · Builders Risk Insurance is included
- Performance and payment bond is included
- Final foundation design is pending. A progress drawing was provided by Mclaren on 4-3-23 and is attached. We feel comfortable that we have covered the cost associated with the current foundation design concept.

Div 02 Existing Conditions

None

Div 03 Concrete

• Concrete slab on grade is per architectural floor plan

Div 03 Precast

- Standard gray color for precast concrete with a picture framed recessed exposed aggregate finish on the spandrel panels. Additional options can be reviewed with the team for the same value of work
- Utilizing precast washes
- Drawings show snow piling location. We do not recommend snow piling in these areas that are shown
- We have assumed the use of the existing Binghamton Plaza Shopping Mall parking lot area for staging precast pieces. We have included a lease allowance of \$30,000

Div 04 Masonry

Ground face CMU figured at "public" locations and is assumed to be color group 1

Div 05 Metal

Steel to be supplied bare and ready to receive fireproofing



Project: Water Street Parking Garage

Page 2 of 5

• Due to the size of several large steel members (i.e. W40, W44, etc.) there are fabrication requirements that may limit the roll dates. We have included \$66,400 within the base bid for early procurement of 3 W44 beams.

Railing systems to be fabricated by Steel Fabricator and galvanized

Div 06 Wood and Plastics

None

Div 07 Thermal & Moisture Protection

- Waterproofing assumed at (2) elevator pits
- Parking structure to be independent of the Boscov building. An opening will be provided in the spandrel panels on the 3rd floor for future walkway

Div 08 Doors & Windows

 Overhead fire curtain is based on the use of FireKing 635 manufactured by Overhead Door Corporation

Div 09 Finishes

- Painting includes accent walls on each floor, HM doors and frames and bollards
- Temporary enclosures at elevator shafts are wall type S2

Div 10 Specialties

• Some signage is shown to be attached directly to the beam portion of the precast tees. This attachment location needs to be reviewed with the precast manufacturer prior to installation. Attachment location subject to change

Div 11 Equipment

We have included an allowance of \$157,000 for parking equipment.

Div 13 Special Construction

None

Div 21 Fire Protection

None

Div 22 Plumbing

We have included 1 internal hose bib per parking level (5 total)

Div 26/27/28 Electrical/Communications/Security

- Rigid conduit and cabling for future apartments is included in the 6th floor apartments breakout in lieu of specified bus duct
- Exterior colored accent lighting is included on every other column along Water and Henry Street

Div 31/32/33 Earthwork/Exterior Improvements/Utilities

• We have included the reuse of existing onsite soils for fills and backfill



Project: Water Street Parking Garage

Page 3 of 5

- Item 4 gravel used for all subbases
- We have not included any underground demolition beyond what is shown on drawing S100
- Landscaping and site furnishings have not been included
- Asphalt at 1st floor slab as shown on Architectural and Civil documents, not structural

Div 31 Steel Piles

- We have included 2ea Static Load Tests (Quick Test Method), one on new and one on existing
- We have included 2ea Dynamic Load Tests, one on new and one on existing
- We have included 2ea Lateral Load Tests, one on new and one on existing
- Pile condition We have not included cutting off existing piles as discussed in the geotechnical report. We believe concrete can be removed without damage to piles

Exclusions

General

- Sales tax
- All investigative testing
- All 3rd Party Testing during construction
- Vibration controls
- Hazardous material removal or disposal
- Building permit/fees
- Flood insurance
- Architectural, structural & civil engineering fees
- M/WBE and/or local participation labor requirements
- Utility company fees associated with relocations, installation and energy usage/consumption by Owner, inclusive of temporary electrical and gas usage
- SWPPP and associated inspections
- Offsite contractor parking, any costs associated with parking is assumed to be absorbed by The City. We assume 50 spaces will be required
- No snow melt/ snow management systems have been included. Owner requirements and discussions need to take place prior to design finalization

Div 02 Existing Conditions

Structural modification to existing building

Div 03 Concrete

Waterproofing under ground floor

Div 03 Precast

 Precast bumpers are no longer required by code. The spandrel panel is designed to accommodate impact load

Div 05 Metals



Project: Water Street Parking Garage

Page 4 of 5

None

Div 06 Wood and Plastics

None

Div 07 Thermal & Moisture Protection

- Damproofing/waterproofing of foundations
- Fireproofing of structural steel at underside of 6th floor deck

Div 08 Doors & Windows

Automatic operators at storefront and HM doors

Div 09 Finishes

- Painting of underside of precast per note 3 on Reflected Ceiling Plans
- · Painting of railings, railings to are galvanized
- · Painting of CMU walls
- Fit out of Lobby/Trash/compactor/etc. space
- · Finished flooring materials

Div 10 Specialties

None

Div 11 Equipment

· Pay on foot machine

Div 12 Furnishings

None

Div 13 Special Construction

None

Div 22 Plumbing

 No insulation or heat trace on domestic water to interior/exterior hose bibs. To be drained in fall

Div 23 HVAC

None

Div 26/27/28 Electrical/Communications/Security

- Power Company Charges
- Vehicle Charging Stations by Owner. Conduit is included in our price only
- Bus duct for apartments (conduit and cabling is provided in lieu of)

Div 31/32/33 Earthwork/Exterior Improvements/Utilities

- Gas service
- Site lighting and electric service
- Removal and replacement of unsuitable soils



Project: Water Street Parking Garage Page 5 of 5

 Heavy duty dewatering, foundation drains, and under slab drains have not been included as the project does not reside in flood zone

· Landscaping and site furnishings

Div 31 Steel Piles

Replacement of existing piles deemed to be unserviceable

Apartment Associated Construction Costs

- If any work associated with the Apartment construction is changed or deleted, then notification to the Contractor needs to be made at time of Contract Award.
- The 6th floor podium has been provided as an add alternate. This alternate must be accepted by 4/28/23 for pricing to hold
 - Summary Alternate scope of work for 6th floor podium
 - Extension of precast columns to support structural framing as shown on S-106a and S-106b
 - Addition of structural steel framing and decking and associated embeds as shown on S-106a and S-106b
 - Placement of the concrete slab on deck and associated reinforcing as shown on S-106a and S-106b
 - Installation of the electrical service conduit and cabling that would service the apartments as well as the empty data conduits from 1st floor to 6th floor as shown on E-100, E-112 through E-115
 - Installation of 5^{TH} floor deck mounted lighting as shown on E-115. The intent would be to replace this lighting with pole mounted fixtures
 - Installation of the 5th floor fire protection system per as shown on FP115
 - Installation of the fire protection service to future apartments on shown on FP301
 - Installation of the domestic water, storm and sanitary/waste and vent piping as shown on P111 through P115

Alternate List & Descriptions

Pike

Page 1 of 1


Project: Water Street Parking Garage

04 - Alternate List and Description

• Add Alternate - 6th Floor Podium


- o Alternate Description:
 - Extension of precast columns to support structural framing as shown on S-106a and S-106b
 - Addition of structural steel framing and decking and associated embeds as shown on S-106a and S-106b
 - Placement of the concrete slab on deck and associated reinforcing as shown on S-106a and S-106b
 - Installation of the electrical service conduit and cabling that would service the apartments as well as the empty data conduits from 1st floor to 6th floor as shown on E-100, E-112 through E-115
 - Installation of 5^{TH} floor deck mounted lighting as shown on E-115. The intent would be to replace this lighting with pole mounted fixtures
 - Installation of the 5th floor fire protection system per as shown on FP115
 - Installation of the fire protection service to future apartments on shown on FP301
 - Installation of the domestic water, storm and sanitary/waste and vent piping as shown on P111 through P115





Ž.

PINE



M.G. McLaren Engineering and Land Surveying, F 1,800,420,6401 | www.rigmclaren.com

, z

CITY OF BINGHAMTON


WATER ST. PARKING STRUCTURE


REV. # DESCRIPTION DATE
ISSUED FOR PRICING 222/223


SIXTH FLOOR FRAMING PLAN -AREA B


S-106b


RECEIVED





































TYPICAL PRECAST SPANDREL PANEL

